





## POST - FUKUSHIMA IMPROVEMENT OF THE EMERGENCY PLAN FOR THE TIHANGE AND DOEL NUCLEAR POWER PLANTS IN BELGIUM

**Namiddag rond Nucleair Noodplan, Huidige Stand van  
Zaken, Lessen en Perspectieven (BVS-ABR)**

Brussels – 17<sup>th</sup> May 2013

Katja Cauwenbergh, Benoit Lance, Els Thoelen, Sébastien Bontemps





# **EMERGENCY PLANNING IN A NUCLEAR POWER PLANT**

# WHY AN EMERGENCY PLAN?



**To protect people & environment against radiation exposure**



If radionuclides are released into the environment,  
all efforts and all barriers to avoid this from happening notwithstanding

## OBJECTIVES

- To ensure information of the federal government
- To bring personnel and visitors on the site into safety
- To coordinate the interventions on site and to have them carried out safely \*
- To assess the potential radiological consequences
- To ensure coordination with the external emergency services (if intervening on site)

\* All actions outside the site are carried out by the government

## Organisation de l'urgence au sein d'ELECTRABEL

GDF - Suez

Active l'entraide internationale

Electrabel Corporate Crisis center

Active l'entraide nationale et prend les décisions stratégiques

Cadres d'astreinte du site

Management de crise et contacts avec les autorités

Salle de commande

Appelle les secours et gère la technique

EPI / Pompiers / Ambulanciers / SMUR / Police

Collaborent sur le terrain

## People on site for coping with a nuclear accident

- **During working hours (< 25% of time)**
  - » Everybody
- **Outside working hours (>75% of time)**
  - » Shift personnel
    - Operations
    - Chemistry/Radiation protection
    - Site Security
    - On site fire brigade
  - » On-call team members, effectively on duty
  - » Extra people that are mobilised (by telephone, GSM, .....)

## On-site emergency centers

### Centre Opérationnel de Site (COS) / Noodplankamer

Gestion de la crise par une partie de l'équipe de crise :

- ✓ prises de décision,
- ✓ interface avec les Autorités,
- ✓ suivi des rejets radioactifs,
- ✓ recensement du personnel,
- ✓ communication de crise.



### Salle de commande + annexe (COT/BK)

Gestion de la crise par l'autre partie de l'équipe de crise et par la salle de commande:

- ✓ conduite des installations et gestion de l'incident/accident,
- ✓ suivi de l'état de sûreté des installations,
- ✓ gestion des équipes techniques d'intervention.

## Fall Back Emergency Locations

### On-site

- ✓ OTSC (On-Site Technical Support Center) / COT

### Awirs & Scaldis

- ✓ Preparation of interventions
- ✓ Back-up crisis center location
- ✓ Reception of worker's families
- ✓ (Decontamination facilities)

## On-site emergency locations

### Locaux EPI

Point de rendez-vous des Équipes de première intervention et des secours extérieurs si aucun relais EPI n'a été indiqué.

Présence d'une partie du matériel d'intervention : moyens de communication, extincteurs, moyens de protection individuels, bonbonnes d'air comprimé, masques, chariot anti-pollution, matériel médical, civières, ...



## On-site emergency locations

### Locaux et points de regroupement

Regroupement et recensement du personnel en cas d'accident



Chaque bâtiment a un ou plusieurs locaux de regroupement (hors zone)

Matériel disponible : monitoring de la radioactivité, comprimés d'iode, gants, surbottes, masques, lecteurs de recensement, etc.



Chaque bâtiment a un point de regroupement



## BELGIAN STRESS TESTS OVERVIEW

## Definitie

- Een gerichte herevaluatie van de veiligheidsmarges van nucleaire centrales, in het licht van de gebeurtenissen van Fukushima : extreme natuurlijke voorvallen die de veiligheidsfuncties van de centrale ondermijnen en leiden tot een ernstig (nucleair) ongeval

# BELGIAN STRESS TESTS

## Milestones

**March 11 2011**

Accident @  
Fukushima

**October 31 2011**

Final Report  
delivered at FANC

**June 30 2012**

Consolidated Report  
to the European  
Council

**April 21 2011**

WENRA Stress  
Test specifications



**January –**

**April 2012**  
Peer Reviews

**Dec 31 2011**

Final Report  
verified by FANC

**2013 – 14 - 15**

Action plan

## Stress tests specifications

### Issues highlighted by events in Fukushima, combination of initiating events

#### ■ Initiating events conceivable at the plant site



- ✓ Earthquake
- ✓ Flooding
- ✓ Other extreme natural conditions (tornado, rain, snow,...)
- ✓ *Man-made hazards (airplane crash, cyber attack, gas explosion, toxic gases, explosive gases)*

#### ■ Consequential loss of safety functions

- ✓ Loss of electrical power, including Station Black Out (SBO)
- ✓ Loss of the Ultimate Heat Sink (UHS)
- ✓ Combination of the two

#### ■ **(Severe) Accident management issues and Emergency Preparedness**

## RESULTS

- Onze centrales zijn **robuust + specifieke troeven in vergelijking met andere landen:**
  - ✓ Dubbel containment reactorgebouw
  - ✓ Twee niveaus noodsystemen (bijv 19 dieselaggregaten kunnen elektrische voeding leveren)
  - ✓ Dubbele uitvoering ultieme koude bron (vb. KCD: Scheldewater én noodkoelvijvers)
- Mogelijke **verbeteringsacties gedefineerd**
  - ✓ Heel wat daarvan al lopende in het kader van Tienjaarlijkse Herzieningen en project LTO (Long Term Operations)

# BELGIAN STRESS TESTS

AREA	Principal Improvements
Earthquake	Enhancement of some structures, systems and components (SSC's) (e.g. pipings)
Flooding	Peripheral protection around site of Tihange
Electric Power	Alternative electric power supply by additional equipment , connections, cables, breakers
Water Supply	Alternative water supply by additional equipment and hydraulic connections
Severe Accident Management	Filtered Containment Vents
<b>Emergency Planning</b>	Focus on multi units event induced by extreme external conditions



## **IMPROVEMENTS IN THE DOMAIN OF EMERGENCY PLANNING AND PREPAREDNESS**

## IMPROVEMENTS IN THE DOMAIN OF EPP

- The **objective** of the Post Fukushima project is to prepare the plant for **larger** scale disasters and implies an extension of available personnel and **equipment**

# IMPROVEMENTS IN THE DOMAIN OF EPP

AREA	Principal Improvements
Organization	<ul style="list-style-type: none"> <li>Development of a new mode "High": Enhanced emergency organization for multi-unit accident</li> </ul>
Logistics	<ul style="list-style-type: none"> <li>New Nuclear Logistic Support Cell (NLSC) to be created at Corporate level</li> </ul>
Communication means	<ul style="list-style-type: none"> <li>Additional communication means – enhanced use of satellite communications</li> </ul>
Infrastructure	<ul style="list-style-type: none"> <li>Construction of a new on-site emergency center @ Tihange</li> </ul>
Radiological dispersion models	<ul style="list-style-type: none"> <li>Upgrade of the code for the calculation of atmospheric radioactive releases</li> </ul>
Work @ contaminated site	<ul style="list-style-type: none"> <li>Guidance / Additional RP means</li> <li>Fixation of contamination – mngmt of large volumes (potentially contaminated water)</li> </ul>

## 3 OPERATIONAL LEVELS


- The emergency management organization of Electrabel will work according to three operational levels:
  - ✓ A “**standard** level”, currently in force
  - ✓ An “**alert level**”\* with preventive measures in case of predictable events such as flooding affecting the whole nuclear site
  - ✓ A “**high level**”, foreseen to cope with unpredictable events affecting more than one unit at the same nuclear site.

---

\* “**alert** level” mainly consists in having on-call crisis team already present at the site, in shift, during the pre-defined “alert” phases. This period is also used to take all preventive additional measures.

## TIME LINE IN MODE HIGH

Extended fleet assistance is provided (NLSC), that will be operational at the latest 24 hours after activation of the mode HIGH



### $t_0$ Extreme external event

As dimensioning assumption, the site must have the necessary material to be autonomous up to  $t_0 + 72h$

It is most probable to reach the site with heavy equipments and large fuel supply for diesel operated engines, as well as needed manpower.


# NON CONVENTIONAL MEANS (1)

Non conventional means to avoid cliff edge effects:

- Alternative 380V means to source batteries, pumps, compressors ,valves
- Mobile pumps and fire hoses connected to available water sources



## NON CONVENTIONAL MEANS (2)




# NUCLEAR LOGISTIC SUPPORT CELL



**OBJECTIVE:** relieve the operator at affected site of logistic tasks organized outside of the site

## TASKS

- **Coordination** , through a Liaison Officer (LO), sent to the affected site, in mode high, in order, for him, to understand and cover their needs in Logistical Support (extra means & manpower)
- **Preparation** of Logistical Support (extra means & manpower) :
  - ✓ Extra means, i.e.: equipment & goods stored in specific warehouses or available under contract with suppliers (NCM, refueling capacity, protective equipment, RP & decontamination means, remote handling technology, special tools, catering,...)
  - ✓ Extra manpower, i.e.: human resources available from Electrabel, GDF SUEZ, or contractors.
- **Transfer** of Logistical Support to the affected site through a backup infrastructure (fixed or mobile) located as close as possible of the affected site, operational less than 24h after activation of NLSC by Corporate Crisis Center



## Support from KHG (Germany)

- ✓ Infrastructure Group for Transportation, Communication, Power supply
- ✓ Radiation Protection Group for Measurement and Protection
- ✓ Decontamination Group for mobile Decontamination
- ✓ Remote Handling Group for access to areas with high dose rate





## REMOTE HANDLING TECHNOLOGY

## Enhanced use of satellite communications

- Deploying wireless communications is typically among the first priorities in any emergency situation
- In the context of the emergency plan, both sites possess **diverse and redundant means of communication.**
- When setting up this communications infrastructure, however, possible extreme scenarios such as examined here were not taken into consideration.



It is intended for each site to possess an "**ultimate**" **communication system** in order to meet a number of **basic communication needs** in the given circumstances. Such system should :

- ✓ **operate on wireless (satellite) technology**
- ✓ with an autonomy larger than 72h, and
- ✓ should be rapidly deployed by someone who has a minimum of training to do this (plug & play, etc.)



## Construction of new on-site emergency center @ Tihange

- La localisation et la structure actuelle du bâtiment abritant le COS ne garantissent pas une fonctionnalité absolue en cas de conditions externes très dégradées (séisme notamment)
- Le COT de chaque unité est équipé de manière à pouvoir servir de COS de repli en cas de perte du COS principal


### → Construction d'un nouveau COS

- ✓ Hors inondation
- ✓ Résistant au DBE (design base earthquake)
- ✓ Pourvu d'une infrastructure de décontamination
- ✓ Secouru par groupe **électrogène** indépendant
- ✓ Pourvu des dispositifs de filtration de l'air extérieur

# RADIOLOGICAL DISPERSION MODELS

## Upgrade of the code for atmospheric radioactive releases calculations

- ✓ Multi-unit releases
- ✓ Long duration of releases (> 24 h)
- ✓ Longer range for releases
- ✓ Use of different meteo data
- ✓ Etc.



# WORK MNGMT @ CONTAMINATED SITE

- ✓ Guidance / Additional RP means
- ✓ Fixation of contamination – mngmt of large volumes (potentially contaminated water)





**TO SUM UP**

## TO SUM UP

- Onze centrales zijn **robuust** + specifieke **troeven** in vergelijking met andere landen:
  - ✓ Dubbel containment reactorgebouw
  - ✓ Twee niveaus noodsystemen
  - ✓ Dubbele uitvoering ultieme koude bron
- Mogelijke verbeterpistes kunnen ons helpen verder te werken aan continue verbetering

**Vous avez l'énergie.**

**Electrabel**  
*GDF SUEZ*